## KADUR DIVISION.

*The 10th June* 1896.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 10th July 1896, for constructing a Taluk Cutcherry at Kadur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Taluk Cutcherry at Kadur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

| *Description of work.* | *Per.* | *Quantity.* |
|---|---|---|
| Excavating foundation | C.yds. | 418 |
| Filling foundation with stone in mortar | C.ft. | 9,822 |
| Basement do do | Do | 3,238 |
| Superstructure, burnt brick in mortar | Do | 16,487 |
| Arch work do do | Do | 1,117 |
| Stone slabs dressed finely for steps | S.ft. | 369 |
| Do for lintles | Do | 119 |
| Plastering with chunam | Sqr. | 241·27 |
| Color washing | Do | 85·68 |
| White washing | Do | 170·82 |
| Pointing with chunam | Do | 9·75 |
| Teakwood doors battened including frame with lock, &c., complete | S.ft. | 569 |
| Do do with iron work for Treasury | Do | 23 |
| Teakwood windows battened and glazed with iron bars 1″ (dia.) | Do | 406 |
| Teakwood ventilators with glazed shutters with iron bars ¾″ (dia.) | Do | 70 |
| Teakwood lower windows for side rooms | Do | 14 |
| Teakwood entrance gate with strong iron work, &c., complete | Do | 57 |
| Teakwood windows for prison with battened shutters and iron bars 1″ (dia.) | Do | 96 |
| Brick in chunam column | Lump sum in Rupees. | |
| Chocolate painting on doors and windows | Sqr. | 25·00 |
| Teakwood railing between Treasury and Sheristadar's seat | R. ft. | 45 |
| Teakwood work | C.ft. | 473·06 |
| Teakwood planking for lock-up rooms | S.ft. | 636 |
| Roofing with 1st class Mangalore tiles and teak reepers, complete, &c. | Sqr. | 6,174 |
| Ridging with do | R.ft. | 336 |
| Flat terrace to Treasury | Sqr. | 1·15 |
| Bengal terrace | Do | 19·08 |
| Flooring with flag stones | S.ft. | 15·27 |
| Flooring with concrete and plastering over it | C.ft. | 1,372 |
| Dental cornice work, ornamental, as per plan | R.ft. | 174 |
| Do plain | Do | 876 |
| Do above plinth of pillar | Do | 250 |
| Ornamental finials | No. | 4 |
| Wood oiling | Sqr. | 40·00 |
| Whiteant composition | Do | 20·00 |
| Bamboo outer rind matting | Do | 23·67 |
| Zinc gutters for valley of roof | R.ft. | 50 |
| Clearing site, filling pits and compensation for land, &c. | Lump sum in Rupees. | |

D. RANGA RAO, *Offg. Executive Engineer.*